

Site Key Layout Scale 1:5000

Site Layout Scale 1:1000



ROCKHAMPTON REGIONAL COUNCIL APPROVED PLANS

These plans are approved subject to the current conditions of approval associated with **Development Permit No.:** D/96-2024 Dated: 16 December 2024

PeaceField Egg Farms

Building Design

Preliminary

| | risions Description | | Date | Drawn | Check |
|---|------------------------|--|--------|-------|-------|
| 1 | Revision 1 | | Date 1 | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |


Peacefield Rockhampton


-Address 6 Smalls Road **Hamilton Creek** QLD 4714

| Farm Layout | |
|---------------------------|-----------------------------|
| Drawn Design DRK | |
| Project Number 3D24006 | Scale at A3 As indicated |
| Drawing Number | |


etatio

acking Shed





PROPOSED EGG FARM EXPANSION 4-6 SMALLS RD, MT MORGAN FOR SANTREV PTY LTD



ROCKHAMPTON REGIONAL COUNCIL

APPROVED PLANS

These plans are approved subject to the current conditions of approval associated with

Development Permit No.: D/96-2024

Dated: 16 December 2024

LOCALITY PLAN ROCKHAMPTON REGIONAL COUNCIL LOT 1 ON MPH12210, LOT 2 ON MPH14362 & LOT 1 ON MPH11307

| BEFORE YOU DIG www.byda.com.gu |
|--------------------------------------|
|--------------------------------------|

INDEMNITY - EXISTING SERVICES

NOT WITHSTANDING THAT EXISTING SERVICES MAY OR MAN NOT BE SHOWN ON THESE DRAWINGS, NO RESPONSIBILITY IS TAKEN BY THE ENGINEER OR THE PRINCIPAL FOR THIS INFORMATION WHICH HAS BEEN SUPPLIED BY OTHERS. THE DETAILS ARE PROVIDED FOR INFORMATION ONLY. THE CONTRACTOR SHALL ASCERTAIN THE POSITION OF ALL UNDERGROUND SERVICES PRIOR TO EXCAVATION AND SHALL BE RESPONSIBLE FOR THE COST OF REPAIRS TO DAMAGES CAUSED AS A RESULT OF THE WORKS.

LEVEL AND COORDINATE DATUM INFORMATION PSM 752941 MGA2020 ZONE 56 LOCATION: HALL STREET, MOUNT MORGAN E: 233582.444 N: 7382336.122 AHD: 253.009m

FOR OPERATIONAL WORKS APPROVAL

| - | | | _ | | | | | |
|------------|----------|------------------------------------|-----|-----|--|--|--|--|
| | | | | | | | | |
| | | | | | | | | |
| | | | | | | | | |
| | | | | | | | | |
| 27/06/2024 | Α | FOR OPERATIONAL WORKS APPROVAL | AB | CWS | | | | |
| 05/06/2024 | 1 | PRELIMINARY - NOT FOR CONSTRUCTION | AB | CWS | | | | |
| DATE | REV | DESCRIPTION | REC | APP | | | | |
| | ND//CONC | | | | | | | |

ROCKHAMPTON OFFICE
21 EAST STREET
PO BOX 264
ROCKHAMPTON, QLD, 4700
PH: (07) 4829 3660
WEB: www.premise.com.au

| DESIGNED A.BURGGRAAFF | SCALE | 40 | 80 | 120m | CLIENT | SANTREV PTY LTD | JOB CODE | |
|---------------------------|-------|------------|--------------|-------|-------------|---|--------------|-----|
| CHECKED C.SHIELDS | Ĕ | SCALE 1 | :2000 (A1) | 12011 | PROJECT | PROPOSED EGG FARM EXPANSION | P00154 | 40 |
| PROJECT MANAGER | | SCALE 1 | .2000 (A1) | | | | | |
| CHRIS SHIELDS | | | | | LOCATION | 4-6 SMALLS RD. MOUNT MORGAN | | 1 |
| ENGINEERING CERTIFICATION | | | | | LUCATION | 4-0 SMALLS RD, MOUNT MORGAN | SHEET NUMBER | REV |
| CAMOR | | | | | SHEET TITLE | COVER SHEET, LOCALITY PLAN & DRAWING SCHEDULE | C001 | A |
| CHRIS SHIELDS RPEQ 9347 | | ORIGINAL S | HEET SIZE A1 | | | COVER SHEET, ECCRETT I EAR & DRAWING SCHEDOLE | | |
| | | | | | | | | |

| | DRAWING SCHEDULE | | | | |
|-------------|--|--|--|--|--|
| DRAWING NO. | DRAWING TITLE | | | | |
| C001 | COVER SHEET, LOCALITY PLAN & DRAWING SCHEDULE | | | | |
| C002 | SAFETY IN DESIGN REPORT | | | | |
| C003 | GENERAL NOTES | | | | |
| C004 | EXISITING SITE PLAN | | | | |
| C100 | EARTHWORKS LAYOUT PLAN | | | | |
| C101 | EARTHWORKS SITE SECTIONS | | | | |
| C200 | ROAD GEOMETRY PLAN | | | | |
| C210 | ROADWORKS & STORMWATER DRAINAGE PLAN | | | | |
| C220 | ROAD LONGITUDINAL SECTION | | | | |
| C230 | ROAD CROSS SECTION SHEET 1 OF 7 | | | | |
| C231 | ROAD CROSS SECTION SHEET 2 OF 7 | | | | |
| C232 | ROAD CROSS SECTION SHEET 3 OF 7 | | | | |
| C233 | ROAD CROSS SECTION SHEET 4 OF 7 | | | | |
| C234 | ROAD CROSS SECTION SHEET 5 OF 7 | | | | |
| C235 | ROAD CROSS SECTION SHEET 6 OF 7 | | | | |
| C236 | ROAD CROSS SECTION SHEET 7 OF 7 | | | | |
| C600 | SOIL EROSION & SEDIMENT CONTROL - LAYOUT PLAN | | | | |
| C601 | SOIL EROSION & SEDIMENT CONTROL - DETAILS PLAN | | | | |

| | | | GN HAZARD SC | IILDOLL | |
|------|---|---|--------------|---|------------------|
| ITEM | DESIGN HAZARD | POTENTIAL HAZARD | RISK | ELIMINATION / MINIMISATION OF HAZARD / RISK | RESIDUAL RISK |
| D1 | ROAD DESIGN HAZARD | INTERNAL ROADS AND ACCESSES CONNECTING TO THE EXISTING INTERNAL ACCESS ROAD NETWORK MUST BE DESIGNED TO SUIT A 19m SEMI IN THE SOUTHERN AREA AND A 26m B-DOUBLE IN THE NORTHERN AND WESTERN AREAS. | MODERATE | ALL INTERNAL ROADS AND ACCESSES HAVE BEEN DESIGNED TO ACCOMMODATE TURNING MOVEMENTS FOR THE DESIRED VEHICLES. | LOW |
| D2 | SITE DRAINAGE HAZARD | SITE MUST DRAIN EFFECTIVELY IN BOTH MINOR AND MAJOR RAIN EVENTS, ENSURING THAT NEIGHBOURING PROPERTIES AND CATCHMENTS ARE NOT NEGATIVELY IMPACTED. | HIGH | STORMWATER NETWORK AND SITE GRADING HAVE BEEN DESIGNED TO ENSURE THAT ALL STORMWATER FLOWS ARE DIRECTED TO EXISTING DISCHARGE POINTS | LOW |
| D3 | EXISTING UNDERGROUND / OVERHEAD SERVICES HAZARD | EXISTING UNDERGROUND AND/OR OVERHEAD SERVICES HAZARD EXIST ON SITE. | MODERATE | SITE HAS BEEN DESIGNED TO PREVENT THE NEED FOR RELOCATION OF KNOWN EXISTING SERVICES WHERE POSSIBLE. CONTRACTOR IS RESPONSIBLE FOR CONDUCTING FURTHER CHECKS. | LOW |

DESIGN HAZARD NOTES:

- HEALTH AND SAFETY ACT 2011 QLD.

- REOUIRED FOR DESIGNS THAT HAVE TYPICAL FEATURES.

CONSTRUCTION HAZARD NOTES:

- AND SAFE WORK METHOD STATEMENTS FOR THE SITE.
- THE CONSTRUCTION HAZARD SCHEDULE.

| LEVEL | |
|-------------------|--|
| 5 - CATASTROPHIC | FATALITY OR MULTIPLE EFFECTS OR INABILITY 1 |
| 4 - MAJOR | EXTENSIVE INJURIES, OF EFFECTS TO SINGLE PER IRREVERSIBLE HEALTH E |
| 3 - MODERATE | MEDICAL TREATMENT R PERSON. MULTIPLE PER |
| 2 - MINOR | FIRST AID, SINGLE OR M PERSON ONSITE WITH M |
| 1 - INSIGNIFICANT | NO INJURIES. OVER EXP HEALTH EFFECTS. |
| | |

| LEVEL | DESCRIPTION | QUANTIFICATION GUIDE |
|--------------------|--|----------------------------|
| A - ALMOST CERTAIN | THE EVENT IS EXPECTED TO OCCUR IN MOST CERTAIN CIRCUMSTANCES | MORE THAN ONCE PER YEAR |
| B - LIKELY | THE EVENT <u>WILL</u> PROBABLY OCCUR IN MOST CIRCUMSTANCES | AT LEAST ONCE IN 5 YEARS |
| C - POSSIBLE | THE EVENT <u>SHOULD</u> OCCUR AT SOME TIME | AT LEAST ONCE IN 10 YEARS |
| D - UNLIKELY | THE EVENT <u>COULD</u> OCCUR AT SOME TIME | AT LEAST ONCE IN 30 YEARS |
| E - RARE | THE EVENT MAY OCCUR IN EXCEPTIONAL CIRCUMSTANCES | LESS THAN ONCE IN 30 YEARS |

| | | | | CONSEQUENCE | | |
|------------|---|----------------------|------------------------|-----------------------|----------------------|------------------|
| | | 1 - INSIGNIFICANT | 2 - MINOR | 3 - MODERATE | 4 - MAJOR | 5 - CATASTROPHIC |
| | A - ALMOST CERTAIN | MODERATE | HIGH | EXTREME | EXTREME | EXTREME |
| DOC | B - LIKELY | MODERATE | HIGH | HIGH | EXTREME | EXTREME |
| LIH | C - POSSIBLE | LOW | MODERATE | HIGH | EXTREME | EXTREME |
| LIKELIHOOD | D - UNLIKELY | LOW | LOW | MODERATE | HIGH | EXTREME |
| _ | E - RARE | LOW | LOW | MODERATE | HIGH | HIGH |
| | | | RISK EVALUAT | ION TABLE | | |
| | RISK LEVEL | | | ACTION REQUIRED | | |
| | EXTREME | UNACCEPTABLE RISK. F | RE-DESIGN REQUIRED. DO | NOT PROCEED WITHOU | T ADDITIONAL CONTROL | -S. |
| | HIGH | UNACCEPTABLE RISK. A | ADDITIONAL CONTROLS I | NEEDED. CONSIDER FURT | HER REVIEW AND CONSI | DER RE-DESIGN |
| | MODERATE RISK MAY BE ACCEPTABLE. MANAGEMENT TO DETERMINE ACTIONS REQUIRED | | | | | |
| | LOW | ACCEPTABLE. MANAGE | RISK THROUGH ROUTIN | E PROCEDURES AND OTH | ER ADMINISTRATIVE CO | NTROLS |
| | LUW | ACCEFTABLE. MANAGE | | L FROCEDORES AND OTH | | |

ROCKHAMPTON REGIONAL COUNCIL

APPROVED PLANS

These plans are approved subject to the current conditions of approval associated with **Development Permit No.:** D/96-2024 Dated: 16 December 2024

CONSTRUCTION HAZARD SCHEDULE

| ITEM | POTENTIAL HAZARD | POSSIBLE PREVENTATIVE ACTION | C - P |
|------|--|--|------------|
| C1 | DEEP EXCAVATION HAZARD | ALL STEPS MUST BE TAKEN TO OBTAIN CURRENT UNDERGROUND SERVICES INFORMATION BEFORE EXCAVATION WORKS COMMENCE. EXCAVATION WORK MUST BE UNDERTAKEN BY APPROPRIATELY EXPERIENCED AND QUALIFIED PERSONNEL. EXCAVATIONS SHALL BE ADEQUATELY SHORED AND APPROPRIATE BARRICADES AND SIGNAGE ERECTED, IF REQUIRED. | D - L |
| C2 | OVERHEAD POWER HAZARD | WARNING SIGNS AND MARKERS SHALL BE ERECTED ADVISING OF THE PRESENCE OF LIVE OVERHEAD CABLES. A REPRESENTATIVE OF THE SUPPLY AUTHORITY SHALL REMAIN ON SITE DURING EARTHWORKS AND ANY OTHER HIGH RISK WORKS, IF REQUIRED. | E - R |
| C3 | UNDERGROUND ELECTRICAL, TELECOMMUNICATION, GAS AND WATER MAIN HAZARD | WARNING SIGNS AND MARKERS SHALL BE ERECTED ADVISING OF THE PRESENCE OF THE EXISTING SERVICE. THE SERVICE SHALL BE IDENTIFIED AND MARKED BY THE SUPPLY AUTHORITY PRIOR TO THE COMMENCEMENT OF EXCAVATION. A REPRESENTATIVE OF THE SUPPLY AUTHORITY SHALL REMAIN ON SITE DURING THE EXCAVATION WORK, IF REQUIRED. | |
| C4 | WORKS NEAR RAIL, AIRPORTS AND ROADS HAZARD | ALL REQUIRED PERMITS, APPROVALS AND SAFETY REQUIREMENTS FROM THE RELEVANT AUTHORITY SHOULD BE OBTAINED PRIOR TO COMMENCING WORK. A REPRESENTATIVE OF THE RELEVANT AUTHORITY SHOULD BE OBTAINED PRIOR TO COMMENCING WORK. A REPRESENTATIVE OF THE RELEVANT AUTHORITY SHOULD BE OBTAINED PRIOR TO COMMENCING WORK. A REPRESENTATIVE OF THE RELEVANT AUTHORITY SHOULD BE OBTAINED PRIOR TO COMMENCING WORK. A REPRESENTATIVE OF THE RELEVANT AUTHORITY SHOULD BE OBTAINED PRIOR TO COMMENCING WORK. A REPRESENTATIVE OF THE RELEVANT AUTHORITY SHOULD BE OBTAINED PRIOR TO COMMENCING WORK. A REPRESENTATIVE OF THE RELEVANT AUTHORITY SHOULD BE OBTAINED PRIOR TO COMMENCING WORK. A REPRESENTATIVE OF THE RELEVANT AUTHORITY SHOULD BE OBTAINED PRIOR TO COMMENCING WORK. | |
| C5 | PEDESTRIAN ACCESS HAZARD | WORK WITHIN OR ADJACENT TO AREAS WHICH THE PUBLIC REQUIRES PEDESTRIAN ACCESS MUST HAVE APPROPRIATE BARRICADES AND SIGNAGE ERECTED AT ALL TIMES. | LIKELIHOOD |
| C6 | POTENTIAL VEHICLE HAZARD | SITE PERSONNEL SHALL BE ADVISED OF THE POTENTIAL HAZARDS AND THE APPROPRIATE PROCEDURES FOR WORKING ADJACENT TO OPERATING PUBLIC ROADS. APPROPRIATE SAFETY CLOTHING SHALL BE WORN AND THE REQUIRED SIGNAGE SHALL BE ERECTED. THE WORKS SHALL BE UNDERTAKEN IN A MANNER WHICH DOES NOT COMPROMISE THE SAFETY OF THE VEHICLE OCCUPANTS OR THE SITE PERSONNEL. | LIKEL |
| C7 | DEMOLITION AND CLEARING HAZARD | SUITABLE QUALIFIED AND EXPERIENCED PERSONNEL SHALL BE RESPONSIBLE FOR THE DEMOLITION AND CLEARING WORKS FOR THE PROJECT AT ALL TIMES. THE CONTRACTORS WORK METHOD STATEMENT SHALL ALSO GIVE CONSIDERATION TO FALLING DEBRIS, COLLAPSE AND DANGEROUS AIRBORNE AGENTS. | |
| C8 | TRAFFIC MANAGEMENT HAZARD | SUITABLE QUALIFIED AND EXPERIENCED PERSONNEL SHALL BE RESPONSIBLE FOR THE SAFE AND ORDERLY PASSAGE OF VEHICULAR AND PEDESTRIAN TRAFFIC THROUGH THE PROJECT AT ALL TIMES. THE CONTRACTOR SHALL DEVELOP A TRAFFIC MANAGEMENT PLAN (TMP) FOR THE PROJECT TO ESTABLISH APPROPRIATE CONTROLS IN ACCORDANCE WITH THE MANUAL FOR UNIFORM TRAFFIC CONTROL. | |
| С9 | ASBESTOS HAZARD | ALL PERSONNEL SHOULD BE ADVISED OF THE POTENTIAL PRESENCE OF ASBESTOS AND AN IDENTIFICATION AND ACTION PLAN SHALL BE PUT IN PLACE. SAMPLING AND IDENTIFICATION IS TO BE UNDERTAKEN IN ACCORDANCE WITH WORKPLACE HEALTH AND SAFETY REGULATIONS. IF SAMPLING CONFIRMS THE PRESENCE OF ASBESTOS THEN THE ACTION PLAN IS TO BE IMPLEMENTED TO REMEDIATE THE SITE. | |
| C10 | POTENTIAL ROCK FALL | LAND ABOVE THE SITE HAS BEEN CLEARED AND SOME EARTHWORKS HAS BEEN UNDERTAKEN CREATING A POTENTIAL ROCK FALL HAZARD. SUITABLE PERSONNEL SHALL BE RESPONSIBLE FOR IDENTIFYING ANY POTENTIAL HAZARD AND THE CONTRACTOR SHALL TAKE APPROPRIATE ACTION TO ELIMINATE THE HAZARD. | |

FOR OPERATIONAL WORKS APPROVAL

| • | ••• | | _ | |
|------------|-----|------------------------------------|-----|-----|
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| 27/06/2024 | Α | FOR OPERATIONAL WORKS APPROVAL | AB | CWS |
| 05/06/2024 | 1 | PRELIMINARY - NOT FOR CONSTRUCTION | AB | CWS |
| DATE | REV | DESCRIPTION | REC | APP |



| DESIGNED A.BURGGRAAFF | SCALE | CLIENT | SAN |
|----------------------------------|------------------------|-------------|-----------------------------|
| C.SHIELDS | | PROJECT | PROPOSED EGG FARM EXPANSION |
| PROJECT MANAGER CHRIS SHIELDS | | | |
| ENGINEERING CERTIFICATION | | LOCATION | 4-6 SMALLS RD, MOUNT MORGAN |
| | | SHEET TITLE | SAFETY IN DESIGN REPORT |
| CHRIS SHIELDS RPEQ 9347 | ORIGINAL SHEET SIZE A1 | | |

1. PREMISE AUSTRALIA PTY LTD (PREMISE), HAVING BEEN COMMISSIONED TO CARRY OUT DETAILED DESIGN AND DOCUMENTATION OF THESE WORKS, CONFIRM THAT THE PREMISE DRAWING SET HAS BEEN INTERNALLY REVIEWED FOR DESIGN SAFETY IN ACCORDANCE WITH SECTION 22 OF THE WORK

 THIS REPORT SUMMARISES AN INTERNAL REVIEW OF THE PREMISE DETAILED DESIGN DRAWINGS FOR DESIGN SAFETY.
 THIS REPORT IN NO WAY RELIEVES THE PRINCIPAL, CONTRACTOR OR ANY OTHER PARTY OF THEIR OWN OBLIGATIONS AND RESPONSIBILITIES UNDER THE WORK HEALTH AND SAFETY ACT 2011 QLD, INCLUDING (BUT NOT LIMITED TO) CONSULTATION WITH THE DESIGNER UNDER SECTION 294 OF THE ACT, THE PREPARATION OF SATISFACTORY SAFE WORK METHOD STATEMENTS AND DUTIES OF CARE.

4. IT IS A REQUIREMENT UNDER SECTION 296 OF THE WORK HEALTH AND SAFETY ACT 2011 QLD, THAT A COPY OF THIS REPORT BE PROVIDED TO THE CONTRACTOR BY THE ENTITY COMMISSIONING THE WORK SHOWN ON THE PREMISE DRAWINGS.

5. AS PER THE DEPARTMENT OF JUSTICE AND THE ATTORNEY-GENERAL- WORKPLACE HEALTH AND SAFETY QUEENSLAND, A WRITTEN REPORT IS NOT

1. UNDER THE QUEENSLAND WORK HEALTH AND SAFETY ACT 2011, THE WORK HEALTH AND SAFETY REGULATION 2011 AND OTHER LEGISLATION AND GUIDELINES, THE PRINCIPAL CONTRACTOR HAS SPECIFIC OBLIGATIONS IN RELATION TO THE SAFE OPERATION OF THE SITE AND OF THE WORKS. TO ASSIST THE PRINCIPAL CONTRACTOR IN COMPLYING WITH THESE OBLIGATIONS THE PROJECT DESIGNERS HAVE IDENTIFIED BY DRAWING NOTES. AREAS WHERE POTENTIAL HAZARDS MAY ARISE. THESE NOTES OR ADVICE, SHALL NOT NECESSARILY BE CONSIDERED COMPLETE AND ARE BASED UPON THE DESIGNERS' UNDERSTANDING OF THE SAFETY RISKS ASSOCIATED WITH THE WORKS.

THESE NOTES OR ADVICE SHALL NOT RELIEVE THE PRINCIPAL CONTRACTOR OF ANY OBLIGATION UNDER THE RELEVANT LEGISLATION OR GUIDELINE. THE PRINCIPAL CONTRACTOR SHALL REMAIN RESPONSIBLE FOR THE PREPARATION OF AN APPROPRIATE WORK HEALTH SAFETY MANAGEMENT PLAN

2. PURSUANT TO THE WORK HEALTH AND SAFETY ACT 2011 WE HEREBY ADVISE THAT OUR DESIGN SAFETY REVIEW HAS IDENTIFIED UNUSUAL OR ATYPICAL DESIGN FEATURES THAT MAY PRESENT ADDITIONAL HAZARDS OR RISKS DURING THE CONSTRUCTION PHASE AND THESE ARE LISTED IN

CONSEQUENCE TABLE

| CONSEQUENCE | COST/TIME |
|--|-------------------------------|
| PERSONS ONSITE WITH LIFE THREATENING HEALTH O CONTINUE | HUGE FINANCIAL OR TIME LOSS |
| ONSET OF SEVERE OR LIFE THREATENING HEALTH SON ONSITE. MULTIPLE PERSONS WITH ONSET OF FFECTS. PERMANENT INJURY TO PERSON ONSITE. | MAJOR FINANCIAL OR TIME LOSS |
| QUIRED. IRREVERSIBLE HEALTH EFFECT TO A SINGLE SONS ONSITE WITH REVERSIBLE HEALTH EFFECTS. | HIGH FINANCIAL OR TIME LOSS |
| JLTIPLE INJURIES AMONGST PERSONS ONSITE. SINGLE ODERATE SHORT TERM REVERSIBLE HEALTH EFFECTS. | MEDIUM FINANCIAL OR TIME LOSS |
| SURE TO A SINGLE PERSON ONSITE, BUT NO REPORTED | LOW FINANCIAL OR TIME LOSS |
| LIKELIHOOD TABLE | |

RISK ANALYSIS MATRIX

NTREV PTY LTD

P001540

C002

GENERAL

1.0 EXISTING SERVICES

THE CONTRACTOR SHALL ESTABLISH ALL EXISTING SERVICES WITHIN THE V SHALL BE PROTECTED AGAINST ACCID CONSTRUCTION OF THE WORKS. THE RESPONSIBLE FOR ALL COSTS INCURR EXISTING SERVICES.

2.0 INSPECTIONS

A MINIMUM OF 24 HOURS NOTICE OF AL SHALL BE GIVEN BY THE CONTRACTOR CLIENT/SUPERINTENDENT / ENGINEER INSPECTIONS AT THE FOLLOWING STA

- a. AT SUBGRADE LEVEL
- BASE COURSE FINAL b. c. ALL STORMWATER PRIOR TO BAG

CHECK LEVELS AND TESTING RESULTS INSPECTIONS WHERE APPLICABLE.

EARTHWORKS AND ROADWORKS

1.0 EARTHWORKS

1.1 TOPSOIL

THE CONTRACTOR SHALL STRIP TOPS WORKS AREA IN PRIVATE PROPERTY DIRECTED BY THE SUPERINTENDENT THE NOMINATED STOCKPILE AREA PRI EARTHWORKS. THE CONTRACTOR SHA TEMPORARY STABILISING MEASURES TRANSPORTATION OF AIRBORNE MATE NUISANCE TO NEIGHBOURING PROPER

BULK FILLING 1.2

1.3.1 ROADS

PRIOR TO ANY FILLING THE AREA TO B ROLLED BY FOUR PASSES OF A 10 TON ROLLER / LOADED WATER TRUCK. THE AS TEST ROLLING IN ACCORDANCE WI 3798 WITH INSPECTION CARRIED OUT GEOTECHNICAL TESTING AUTHORITY ENGINEER. THE COST OF PROOF AND DEEMED TO BE INCLUDED IN THE CON SHALL BE PLACED IN LAYERS OF NOT THICKNESS AND COMPACTED TO A MIN DENSITY AS DETERMINED BY AS 1289, SPECIFICATION. TEST FREQUENCY SH QUALITY ASSURANCE TESTING TABLE EARTHWORKS THE CONTRACTOR SHA ARE KEPT IN A STATE SO AS NOT TO A OR EROSION FROM THE WORKS IN THE CONTENT OF THE FILL SHALL BE MAIN PRACTICAL TO OPTIMUM MOISTURE CO COMPACTION OF THE FILL.

1.3.2 SELECT FILL

SELECT FILL MATERIAL SHALL BE IN AC SPECIFICATION TO ENSURE MOISTURE MINIMISED.

GRADING COEFFICIENT SHALL BE BETV GRADING COEFFICIENT IS:

((%PASSING 26.5MM SIEVE-%PASSING 2 4.75MM SIEVE)/100).

SHRINKAGE PRODUCT SHALL BE BETW WHEREBY THE SHRINKAGE PRODUCT (LINEAR SHRINKAGE X %PASSING 0.42)


SOIL TESTING CONFIRMING MATERIAL BY THE CONTRACTOR.

FOR OPERATION

| - | | | _ | |
|------------|-----|------------------------------------|-----|-----|
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| 27/06/2024 | Α | FOR OPERATIONAL WORKS APPROVAL | AB | CWS |
| 05/06/2024 | 1 | PRELIMINARY - NOT FOR CONSTRUCTION | AB | CWS |
| DATE | REV | DESCRIPTION | REC | APP |
| | | | | |

| a. | STANDARD SUBGRADE | 90% |
|----|-------------------|------|
| b. | STANDARD BASE | 100% |
| | | |

| THE EXTENT AND LOCATION OF WORKS AREA. ALL SERVICES DENTAL DAMAGE DURING THE CONTRACTOR SHALL BE RED DUE TO DAMAGE TO | ALL EARTHWORKS FILL ON LOTS IS TO BE LEVEL 1 CERTIFIED IN ACCORDANCE WITH AS3798-1996 WITH EXTENTS SHOWN ON EARTHWORKS PLAN. CERTIFICATION SHALL STATE THAT FILL IS SIMILAR TO THAT DEFINED IN SECTION 6.1.2 OF AS2870.1-1996 AND CAN THUS BE CLASSIFIED AS "CONTROLLED FILL". 1.4 DUST CONTROL THE CONTRACTOR SHALL ENSURE THAT DUST RESULTING FROM THE EARTHWORKS OPERATIONS IS KEPT TO A MINIMUM BY THE APPLICATION OF WATER TO THE WORKS AREA OR BY OTHER APPROVED METHODS AS DIRECTED BY THE | 2.5 THE TOLERANCE REQUIREMENTS ON THE FINISHED SURFACE LEVEL OF ROADS AND KERB AND CHANNEL SHALL BE AS FOLLOWS: SUBGRADE SURFACE +0MM TO -25MM PAVEMENT THICKNESS +20MM TO -10MM WEARING COURSE THICKNESS +10MM TO -0MM FINISHED ROAD a. HORIZONTAL ALIGNMENT <u>+50MM</u> b. VERTICAL/GEOMETRIC TOLERANCE c. PRIMARY TOLERANCE <u>+10MM</u> d. DEVIATION FROM 3M STRAIGHT EDGE 5MM | 4.2 ALL CAST INSITU CONCRETE WORK SHALL BE CARRIED OUT IN ACCORDANCE WITH THE RELEVANT AUSTRALIAN STANDARDS. NOTWITHSTANDING ANYTHING TO THE CONTRARY, NO SEPARATE PAYMENT WILL BE MADE FOR REINFORCING STEEL AND THE COST SHALL BE DEEMED TO BE INCLUDED IN THE VARIOUS CONCRETE ITEMS. ALL CONCRETE WORK SHALL BE CLASS N32 UNLESS OTHERWISE SPECIFIED. 5.0 INLETS & ACCESS CHAMBERS | ASPHALT TESTS BY MANUFACTURER AGGREGATE GRADING BITUMEN CONTENT COMPACTED DENSITY MAXIMUM DENSITY STABILITY FLOW STIFFNESS VOIDS IN AGGREGATE VOIDS FILLED 1 SERIES OF TESTS PER 50 LINEAR METRES LAID. |
|---|--|---|--|---|
| ALL REQUIRED INSPECTIONS R TO THE R. THE ENGINEER REQUIRES AGES OF CONSTRUCTION. | ENGINEER/SUPERINTENDENT DURING ALL PERIODS OF CONSTRUCTION. 1.5 WATER FOR CONSTRUCTION PURPOSES THE PRINCIPAL SHALL NOT SUPPLY WATER FOR USE IN CONSTRUCTION | DEVIATION FROM 3M STRAIGHT EDGE 3MM CROSSFALL ±0.2% f. RATE OF CHANGE OF CROSSFALL ±0.02% PER METRE. STORMWATER DRAINAGE | ALL FIELD INLETS & ACCESS CHAMBERS ALL FIELD INLETS SHALL BE PRECAST CONCRETE PITS OR APPROVED EQUIVALENT AND SHALL BE INSTALLED IN ACCORDANCE WITH THE MANUFACTURERS' SPECIFICATIONS. ANY INSITU CONCRETE WORK SHALL COMPLY WITH AS3600. FIELD INLETS TO BE INSTALLED IN ACCORDANCE WITH CMDG SPECIFICATIONS | STORMWATER SAND BEDDING, ALIGNMENT AND LEVEL INSPECTION AND APPROVAL BY SUPERINTENDENT / ENGINEER OF BEDDING AND LAYING OF STORMWATER PIPE. LEVELS SUPPLIED BY CONTRACTOR AND APPROVED BY SUPERINTENDENT / ENGINEER. |
| ACKFILLING | OF THE WORKS. THE CONTRACTOR SHALL MAKE HIS OWN ARRANGEMENTS FOR OBTAINING WATER FOR THESE PURPOSES. WATER CAN BE PURCHASED FROM COUNCIL WITH PRIOR CONSENT. | 1.0 PIPES ALL PIPES SHALL BE PRECAST CONCRETE PIPE MANUFACTURED TO COMPLY WITH AS4058:1992 OR FIBRE REINFORCED CONCRETE PIPES | ALL NEW FIELD INLETS TO HAVE GALVANIZED STEEL GRATES WITH MINIMUM CLASS D LIDS IN TRAFFICABLE AREAS AND CLASS B MINIMUM WITHIN GRASSED/LANDSCAPED AREAS. | TRENCH BACKFILL 1 FIELD DENSITY TEST PER SECTION OF TRENCH. |
| S WILL BE REQUIRED PRIOR TO | 1.6 REPLACEMENT OF UNSOUND MATERIAL IF DURING PROOF ROLLING OF THE FILL/PAVEMENT AREAS OR IN THE CONSTRUCTION OF CUTS, UNSOUND OR UNSUITABLE MATERIAL IS ENCOUNTERED WHICH IN THE OPINION OF THE ENGINEER IS NOT SUITABLE FOR INCLUSION IN THE FILL, THE CONTRACTOR SHALL EXCAVATE AND REMOVE TO SPOIL AS DIRECTED ON SITE SUCH UNSUITABLE MATERIAL. THE CONTRACTOR SHALL THEN REPLACE THE | TO COMPLY WITH AS4139. ALL PRECAST CONCRETE PIPES SHALL BE CLASS 2 UNLESS NOTED OTHERWISE ON THE DRAWINGS. ALL PIPES SHALL HAVE FLUSH JOINTS AND BE INSTALLED WITH EXTERNAL RUBBER BANDS UNLESS NOTED OTHERWISE ON THE DRAWINGS. ALL POLYVINYL CHLORIDE (UPVC) PIPES AND FITTINGS TO COMPLY WITH AS 1254, AS/NZS 1260, AS 1273, AS/NZS 1477, AS/NZS 2179.2 AND | INSTALLATION OF PRECAST ROAD GULLY UNITS IS TO BE IN ACCORDANCE WITH CMDG SPECIFICATIONS, INSTALLATION OF PRECAST ACCESS CHAMBERS IS TO BE IN ACCORDANCE WITH CMDG SPECIFICATIONS, | EROSION CONTROL ALL DISTURBED AREAS OUTSIDE SEALED OR CONCRETED PAVEMENT AREAS ARE TO BE STABALISED WITH TOPSOIL AND HYDROMULCH OR TURF OR LANDSCAPING BY OTHERS UPON COMPLETION. REFER TO EROSION AND SEDIMENT CONTROL PLAN FOR DETAILS. AS-CONSTRUCTED INFORMATION |
| SOIL FROM THE WHOLE OF THE TO A DEPTH OF 100mm OR AS / ENGINEER AND STOCKPILE IT IN IOR TO COMMENCING BULK ALL BE REQUIRED TO CARRY OUT TO MINIMISE THE ERIAL THAT MAY CAUSE RTIES. | UNSOUND MATERIAL WITH SUITABLE MATERIAL DRAWN FROM THE CUTTING OPERATION ON SITE (IF AVAILABLE), OR FROM A SUITABLE SUPPLIER. 1.7 REPLACEMENT OF TOPSOIL AT THE COMPLETION OF THE BULK EARTHWORKS, ROADWORKS AND SERVICES INSTALLATION AND FOLLOWING APPROVAL OF THE FINISHED SURFACE OF FOOTPATHS AND OTHER FILLED AREAS, THE CONTRACTOR SHALL LIGHTLY TINE UP THE FILL SURFACE AND REPLACES THE STOCKPILED TOPSOIL IN THE AREAS NOMINATED BY THE SUPERINTENDENT. THE FINISHED SURFACE OF THE TOPSOIL SHALL BE LIGHTLY STATIC | AS 2032. ALL PIPES INSTALLED SHALL BE NEW AND FREE FROM ANY DAMAGE OR CRACKS. 2.0 EXCAVATION AND BACKFILLING THE PIPE TRENCHES SHALL BE EXCAVATED TO ALLOW A MINIMUM 100MM OF APPROVED BEDDING TO THE BOTTOM AND ALL SIDES AND TOP OF THE PIPE. ALL BEDDING, SURROUNDS, AND BACKFILL MATERIAL SHALL BE COMPACTED IN MAXIMUM 150MM THICK LAYERS AND A MINIMUM 95% MAXIMUM DRY DENSITY AS DETERMINED BY AS 1289 E. 1.1 OR DENSITY INDEX OF MINIMUM 70% AS DETERMINED BY AS | QUALITY ASSURANCE TESTING TABLE A: SUBGRADE FIELD DENSITY 1 TEST PER 50m OF ROADWAY OR AS NOMINATED BY THE ENGINEER. SOAKED CBR 1 ON EACH REPRESENTATIVE SAMPLE AS DIRECTED BY THE ENGINEER. PREPARATION INSPECTION AND APPROVAL BY ENGINEER PRIOR TO COMMENCEMENT OF PAVING. SURVEY LEVELS | THE BUILDER SHALL PROVIDE LEVELS AND DIMENSION INFORMATION SUITABLE TO CONFIRM TO THE SATISFACTION OF THE SUPERINTENDENT THAT THE WORKS HAVE BEEN CONSTRUCTED TO THE LEVELS AND DIMENSIONS SHOWN ON THE DRAWING. THE BUILDER SHALL PROVIDE ALL AS-CONSTRUCTED INFORMATION NECESSARY FOR THE PREPARATION OF THE AS-CONSTRUCTED PLANS TO COUNCIL REQUIREMENTS. THE MINIMUM INFORMATION REQUIREMENTS ARE AS FOLLOWS: a. DRAINAGE EXTENTS; b. LOCATIONS OF MANHOLES, GULLY PITS AND CULVERTS; c. INVERT LEVELS OF INLET AND OUTLET PIPES AT MANHOLES AND |
| BE FILLED SHALL BE PROOF NNE MINIMUM STATIC MASS E FINAL PASS SHALL BE TREATED ITH TESTING CLAUSE 5.4 OF AS BY THE APPROVED OR THE SUPERINTENDENT / DTEST ROLLING SHALL BE ITRACT LUMP SUM. FILLING MORE THAN 200mm LOOSE NIMUM STANDARD MAXIMUM DRY E1.1 AND SPECIFIED IN THIS HALL BE AS STATED IN THE A. AT ALL TIMES DURING BULK ALL ENSURE THAT THE WORKS ALLOW PONDING ON THE WORKS E EVENT OF RAIN. THE MOISTURE ITAINED AS CLOSE AS IS ONTENT DURING THE | ROLLED AND WATERED TO PRODUCE AN EVEN SURFACE SUITABLE FOR SEEDING AND FERTILISING. 2.0 PAVEMENT 2.1 PAVEMENT MATERIAL THE PAVEMENT MATERIAL SEEDING AND FERTILISING. 2.1 PAVEMENT MATERIAL THE PAVEMENT MATERIAL SEEDING AND CONTAIN NO ORGANIC MATTER. ALL PAVEMENT MATERIAL MUST BE APPROVED BY THE ENGINEER PRIOR TO PLACEMENT. TEST RESULTS SHALL BE MADE AVAILABLE TO PROVE COMPLIANCE WITH THIS SPECIFICATION. THE BASE COURSE MATERIAL SHALL BE TMR TYPE 2.3. 2.2 NO PAVING MATERIAL SHALL BE PLACED IN AN AREA UNTIL ALL SERVICE CONDUITS, DRAINAGE PIPES, HAVE BEEN COMPLETED TESTED AND BACKFILLED UNLESS APPROVED BY THE SUPERINTENDENT / ENGINEER. 2.3 THE MINIMUM COMPACTION TEST REQUIREMENTS SHALL BE AS FOLLOWS: a. STANDARD SUBGRADE 98% b. STANDARD BASE 100% | 1289 E.G.1. ALL BACKFILL UNDER ROAD PAVEMENTS SHALL HAVE A MINIMUM OF 97% MAXIMUM DRY DENSITY AS DETERMINED BY AS 1289 E.1.1. ALL CONCRETE OR REINFORCED FIBRE PIPES TO BE INSTALLED IN ACCORDANCE WITH CDMG REQUIREMENTS ALL REINFORCED CONCRETE BOX CULVERTS TO BE INSTALLED IN ACCORDANCE WITH CMDG REQUIREDMENTS 3.0 LAYING AND JOINTING PIPE LAYING SHALL BEGIN AT THE DOWN STREAM END OF THE LINE WITH THE GROOVED ENDS OF THE PIPE FACING UPSTREAM. THE END OF THE PIPE SHALL BE CLEANED PRIOR TO THE INSTALLATION OF THE EXTERNAL RUBBER BAND FOR RCP PIPES. LIFTING HOLES IN PIPES SHALL BE SECURELY PLUGGED WITH MANUFACTURER PLUGS OR DRY PACK MORTAR PRIOR TO BACKFILLING. ALL DRAINAGE LINES SHALL BE CONSTRUCTED WITH A TOLERANCE OF ± 15MM IN LINE FROM THE ALIGNMENT SHOWN ON THE DRAWINGS OVER ANY 30M LENGTH. ALL PIPES MUST FALL IN THE REQUIRED DIRECTION. 4.0 CONCRETE WORK | PROVIDED BY CONTRACTOR AT DESIGN CHAINAGES PRIOR TO JOINT COUNCIL AND ENGINEER INSPECTION. SUB-BASE PARTICLE SIZE DISTRIBUTION 1 NO REQUIRED OF COMPACTED SAMPLE IF REQUESTED. DISTIBUTION SAMPLE IF REQUESTED. ATTERBERG LIMITS 1 NO REQUIRED OF COMPACTED SAMPLE IF REQUESTED. SOAKED CBR1 1 PER SOURCE. FIELD DENSITY 1 TEST PER 50M OF ROADWAY OR AS NOMINATED BY THE ENGINEER. CONFIRMATION OF INSITU COMPACTED DEPTH BY LEVEL SURVEY PROVIDED BY THE CONTRACTOR AT DESIGN CHAINAGES PRIOR TO INSPECTION BY ENGINEER. BASE PARTICLE SIZE DISTRIBUTION 1 NO REQUIRED OF COMPACTED SAMPLE IF REQUESTED. | GULLY PITS ON LAYOUT PLAN; GULLY PITS ON LAYOUT PLAN; TOP OF MANHOLE AND GULLY PIT LEVELS AT THE CENTRE POINT ON LAYOUT PLAN. INDICATE ACTUAL PIPE SIZES, CLASSES AND GRADES ON THE LAYOUT PLAN; LOCATIONS AND DEPTHS OF ALL SERVICES (E.G. WATER AND DRAINAGE PIPES). ALL DIMENSIONS SHALL BE PROVIDED IN METRES CORRECT TO 2 DECIMAL PLACES. ALL LEVELS SHALL BE ON AUSTRALIAN HEIGHT DATUM (AHD) AND THE AS CONSTRUCTED SURVEY ON GDA94 COORDINATE SYSTEM IN METRES CORRECT TO 3 DECIMAL PLACES; THE "AS CONSTRUCTED" INFORMATION FOR ROADWORKS AND DRAINAGE SHALL BE PROVIDED WITHIN FOURTEEN (14) DAYS ON COMPLETION OF THE WORKS. |
| E INGRESS UNDER THE SLAB IS WEEN 16 AND 34, WHEREBY 2.0MM SIEVE) X (%PASSING VEEN THE RANGE OF 100 TO 300, IS: 25MM SIEVE). . COMPLIANCE IS TO BE PROVIDED | 2.4 AFTER COMPACTION OF THE SUBGRADE IS COMPLETED, THE SUBGRADE SHALL BE PROOF ROLLED IN THE PRESENCE OF THE ENGINEER IF REQUIRED AND ANY AREAS OF UNSUITABLE MATERIAL SHALL BE REMOVED AS DIRECTED. | 4.1 CONCRETE WORK, SIDE DRAINS, SEEPAGE DRAINS, AND OTHER ITEMS NOT SPECIFICALLY COVERED IN THIS JOBS SPECIFICATION SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE RELEVANT DRAWINGS AND/OR ATTACHED SPECIFICATION. | ATTERBERG LIMITS 1 NO REQUIRED OF COMPACTED SAMPLE IF REQUESTED. SOAKED CBR 1 PER SOURCE. FIELD DENSITY 1 TEST PER 50m OF ROADWAY OR AS NOMINATED BY THE ENGINEER. CONFIRMATION OF INSITU COMPACTED DEPTH BY LEVEL SURVEY PROVIDED BY THE CONTRACTOR AT DESIGN CHAINAGES PRIOR TO INSPECTION BY ENGINEER. | ROCKHAMPTON REGIONAL COUNCIL APPROVED PLANS These plans are approved subject to the current conditions of approval associated with Development Permit No.: D/96-2024 Dated: 16 December 2024 |
| | AB CWS AB CWS REC APP | DESIGNED SCALE CHECKED C.SHIELDS PROJECT MANAGER CHRIS SHIELDS ENGINEERING CERTIFICATION CHRIS SHIELDS RPEQ 9347 ORIGINAL SHEET SIZE A1 | CLIENT SANTREV PROJECT PROPOSED EGG FARM EXPANSION LOCATION 4-6 SMALLS RD, MOUNT MORGAN SHEET TITLE GENERAL NOTES | PTY LTD P001540 SHEET NUMBER C003 A |



Site-Based Stormwater Management Plan

6 Smalls Road, Mount Morgan

20 June 2024 J10721 v1.0



ROCKHAMPTON REGIONAL COUNCIL APPROVED PLANS

These plans are approved subject to the current conditions of approval associated with

Development Permit No.: D/96-2024 Dated: 16 December 2024

Job No: J10721 v1.0

Job Name: 6 Smalls Road, Mount Morgan

| Report Name | Date | Report No. | |
|---------------------------------------|--------------|-------------|--|
| Site-Based Stormwater Management Plan | 20 June 2024 | J10721 v1.0 | |

| Project Engineer: | Jack Hu BE Civil (Hons), MIEAust, CPEng, NER, RPEQ E jack@stormw.com.au |
|-------------------|---|
| Reviewed By: | Steve Hughes BE Civil, MIEAust, CPEng, NER, RPEQ 16468 |

Storm Water Consulting Pty Ltd ACN 105 078 377

1/820 Old Cleveland Rd, Carina QLD 4152 07 3398 4992 www.stormw.com.au

Table of Contents

| 1.0 | Int | roduction | 1 |
|------|-------|------------------------------------|---|
| | | | |
| 2.0 | Sit | e Conditions | |
| | 2.1 | Existing Site | 2 |
| | 2.2 | Developed Site | 2 |
| 3.0 | La | wful Point of Discharge | 3 |
| 4.0 | Hy | drologic Modelling | 4 |
| | 4.1 | Rational Method Calculations | 4 |
| | 4.2 | Existing URBS Model | 4 |
| | 4.3 | Developed URBS Model (Unmitigated) | 5 |
| | 4.4 | Developed URBS Model (Mitigated) | 6 |
| 5.0 | Со | nclusions | 8 |
| List | of Ap | pendicies | 9 |



1.0 INTRODUCTION

Storm Water Consulting Pty Ltd was commissioned by Santrev Pty Ltd to prepare a Site-Based Stormwater Management Plan for the proposed development on 6 Smalls Road, Mount Morgan.

This report has been prepared to address the issues of lawful point of discharge and stormwater quantity management for the proposed development.



2.0 SITE CONDITIONS

2.1 Existing Site

Multiple buildings and sheds are located on the site. The balance of the site is vegetated by maintained grass with scattered trees. The site is bound by Smalls Road to the east and by rural properties in all other directions. An existing site plan is presented in Figure 1, Appendix A. A locality plan is presented in Figure 2.1 below. Survey plans of the site are presented in Appendix E.



Figure 2.1 – Locality Plan (Source: Google Earth)

2.2 Developed Site

It is proposed to demolish some of the existing buildings and sheds on the site and to construct 2 new large sheds, as well as a smaller packing shed. New sealed roads are also proposed around the site. A developed site plan is presented in Figure 2, Appendix A. Development plans are presented in Appendix E.



3.0 LAWFUL POINT OF DISCHARGE

A natural gully is located on the adjoining site to the north, i.e. 4 Smalls Road (refer Figure 3.1 below). The site to the north is also understood to be owned by the developer. This gully currently receives flows from the subject site and conveys flows northward toward Keimar Road. It is considered that this natural gully is the lawful point of discharge for the existing site.




Figure 3.1 – Extract from RRPS 2015 v4.4 Interactive Mapping

The natural gully has been mapped as being located within the "Local Catchment DFE", as shown in the figure above. The natural gully is also considered to be the lawful point of discharge for the proposed works.

A section of the upstream end of the natural gully is proposed to be modified through earthworks to form a detention basin. The detention basin would attenuate the increase in runoff created by the proposed works. Details of the detention basin and its associated hydrologic modelling are presented in the following section.



4.0 HYDROLOGIC MODELLING

Hydrologic analysis and modelling were undertaken to assess the stormwater quantity impacts at the lawful point of discharge and to size the necessary mitigation measures in order to minimise impacts. Details of the calculations, modelling and results are presented below.

4.1 Rational Method Calculations

The catchment discharging to Point-1, the lawful point of discharge nominated in the natural gully, is 3.85 hectares in area (refer to catchment plan in Figure 3, Appendix A). Rational Method calculations were undertaken for the catchment. These calculations have been completed in accordance with the parameters recommended in the Queensland Urban Drainage Manual (QUDM, 2016). A summary of the resulting flows is presented in Table 4.1 below. Detailed Rational Method calculations are presented in Appendix C.

| AEP % | Peak Discharge m³/s |
|----------|------------------------|
| 63 | 0.458 |
| 50 | 0.539 |
| 20 | 0.784 |
| 10 | 0.958 |
| 5 | 1.139 |
| 2 | 1.449 |
| 1 | 1.666 |

Table 4.1 – Rational Method Calculation Flow Summary

4.2 Existing URBS Model

URBS hydrologic modelling was undertaken to assess the peak flows at Point-1. A schematic of the existing URBS model is presented in Figure 4, Appendix A. URBS model data files are presented in Appendix D. A summary of the adopted URBS parameters is presented in Table 4.2 below.

| AEP | Storage Coefficient | Non-Linearity Index | Loss | Continuing Rainfall Loss |
|-----|------------------------|------------------------|------|-----------------------------|
| % | α | m | mm | mm/hr |
| 63 | 1.2 | 0.8 | 15 | 2.5 |
| 50 | 1.2 | 0.8 | 15 | 2.5 |
| 20 | 1.2 | 0.8 | 15 | 2.5 |
| 10 | 1.2 | 0.8 | 15 | 2.5 |

Table 4.2 – URBS Model Parameters



| 5 | 1.2 | 0.8 | 15 | 2.5 |
|---|-----|-----|----|-----|
| 2 | 1.2 | 0.8 | 15 | 2.5 |
| 1 | 1.2 | 0.8 | 0 | 2.5 |

A comparison of the Rational Method flows and the existing URBS flows is presented in Table 4.3 below.

| AEP % | Rational Method m ³ /s | Existing URBS m³/s | Difference m³/s | Difference % |
|----------|--------------------------------------|-----------------------|--------------------|-----------------|
| 63 | 0.458 | 0.488 | 0.030 | 6.6 |
| 50 | 0.539 | 0.557 | 0.018 | 3.3 |
| 20 | 0.784 | 0.780 | 0.004 | 0.5 |
| 10 | 0.958 | 1.037 | 0.079 | 8.2 |
| 5 | 1.139 | 1.207 | 0.068 | 6.0 |
| 2 | 1.449 | 1.438 | 0.011 | 0.8 |
| 1 | 1.666 | 1.630 | 0.036 | 2.2 |

Table 4.3 – Comparison of Flows (Rational Method v URBS)

The results above show that the URBS flows compare favourably with the Rational Method flows and are therefore suitable for assessing the effects of the proposed development at the lawful point of discharge.

4.3 Developed URBS Model (Unmitigated)

A schematic of the developed (unmitigated) URBS model is presented in Figure 5, Appendix A. The developed URBS model reflected the change in fraction impervious on the site due to the proposed removal of existing buildings and sheds, as well as the construction of new sheds and the new road. All other model parameters and inputs remained the same as the existing URBS model. A comparison of the existing URBS flows and the developed (unmitigated) URBS flows is presented in Table 4.4 below.

| ······································ | | | | | | | | | |
|--|-----------------------|---|------------------|---------------|--|--|--|--|--|
| AEP % | Existing URBS m³/s | Developed URBS Unmitigated m ³ /s | Increase m³/s | Increase % | | | | | |
| 63 | 0.488 | 0.493 | 0.005 | 1.0 | | | | | |
| 50 | 0.557 | 0.561 | 0.004 | 0.7 | | | | | |
| 20 | 0.780 | 0.802 | 0.022 | 2.8 | | | | | |
| 10 | 1.037 | 1.043 | 0.006 | 0.6 | | | | | |
| 5 | 1.207 | 1.212 | 0.005 | 0.4 | | | | | |

Table 4.4 – Comparison of URBS Flows (Existing v Developed Unmitigated)



| 2 | 1.438 | 1.441 | 0.003 | 0.2 | |
|---|-------|-------|-------|-----|--|
| 1 | 1.630 | 1.633 | 0.003 | 0.2 | |

The above results indicate that peak flows are marginally increased due to the proposed works. Mitigation of peak flows would be required to minimise downstream impacts. The following section presents the specifications of the proposed detention basin and the associated hydrologic modelling results.

4.4 Developed URBS Model (Mitigated)

A schematic of the developed (mitigated) URBS model is presented in Figure 6, Appendix A. The developed URBS model was modified to include a detention basin, located within the natural gully and formed by constructing an earth embankment. Pipes are proposed at the base of the earth embankment to control the flows discharging from the detention basin. A conceptual design of the basin is presented in Figure 7, Appendix A. Table 4.5 below presents a summary of the detention basin specifications adopted in the model.

| Detail | Specification | | | | | |
|---|---------------|-----------|---|--|--|--|
| Volume | | 216 m³ | | | | |
| Surface Area | | 390 m² | | | | |
| Depth | 1 m | | | | | |
| | Level (m AHD) | Area (m²) | Cumulative Storage (m ³) | | | |
| Level-Area-Storage Relationship | 240.5 | 43 | 0 | | | |
| | 241.0 | 215 | 65 | | | |
| | 241.5 | 390 | 216 | | | |
| Outflow Control • 2 / 525 mm dia. RCP @ IL (240.5 m AHD) • 2 metre wide weir @ IL + 0.6 m (241.1 m) | | | | | | |

Table 4.5 – Detention Basin Specification

A comparison of the existing URBS flows and the developed (mitigated) URBS flows is presented in Table 4.6 below.

| AEP % | Existing URBS m³/s | Developed URBS Mitigated m ³ /s | Increase m³/s | Increase % |
|----------|-----------------------|---|------------------|---------------|
| 63 | 0.488 | 0.479 | -0.009 | -1.8 |
| 50 | 0.557 | 0.538 | -0.019 | -3.4 |
| 20 | 0.780 | 0.770 | -0.010 | -1.3 |



| 10 | 1.037 | 1.019 | -0.018 | -1.7 |
|----|-------|-------|--------|------|
| 5 | 1.207 | 1.187 | -0.020 | -1.7 |
| 2 | 1.438 | 1.412 | -0.026 | -1.8 |
| 1 | 1.630 | 1.598 | -0.032 | -2.0 |

The results presented above indicate that the proposed detention basin effectively mitigates all AEP events (up to and including the 1% AEP event) to the existing flow rate. The proposed works are therefore not considered to result in a material worsening on downstream properties.

Detailed URBS modelling results are presented in Appendix D. A conceptual stormwater layout plan is presented in Figure 7, Appendix A. The final location of stormwater pipes and the detention basin will be confirmed during the detailed design stage of the project.



5.0 CONCLUSIONS

This report has been prepared to address the issues of lawful point of discharge and stormwater quantity management for the proposed development on 6 Smalls Road, Mount Morgan.

A natural gully is located on the adjoining site to the north, i.e. 4 Smalls Road. The site to the north is also understood to be owned by the developer. This gully currently receives flows from the subject site and conveys flows northward toward Keimar Road. The natural gully has been mapped as being located within the "Local Catchment DFE". The natural gully is considered to be the lawful point of discharge for the proposed works.

The model results indicate that peak flows are marginally increased due to the proposed works. Mitigation of peak flows would be required to minimise downstream impacts. A detention basin is proposed, which is located within the natural gully and formed by constructing an earth embankment. Pipes are proposed at the base of the earth embankment to control the flows discharging from the detention basin. The model results indicate that the proposed detention basin effectively mitigates all AEP events (up to and including the 1% AEP event) to the existing flow rate. The proposed works are therefore not considered to result in a material worsening on downstream properties.

A conceptual stormwater layout plan is presented in Figure 7, Appendix A. The final location of stormwater pipes and the detention basin will be confirmed during the detailed design stage of the project.

Steve Hughes BE Civil, MIE Aust, CPEng, RPEQ 16468



LIST OF APPENDICIES

APPENDIX A – Figures

APPENDIX B – Photographs

APPENDIX C – Rational Method Calculations

APPENDIX D – URBS Data

APPENDIX E – Plans

APPENDIX A

Figures











| MATER CONSULTING | | | | | |
|---|-------|--------------|---------|--------|---------------------|
| 1/820 Old Cleveland Rd | Date | 19/06/24 | | | |
| Carina QLD 4152 Phone (07) 3398 4992 | Scale | 1:2,000 (A4) | Job No. | J10721 | Existing URBS Model |



| ATER CONSULTING | Спескеа | | | | |
|---|---------|--------------|---------|--------|---------------------|
| | Date | 19/06/24 | | | Developed URBS |
| Carina QLD 4152 Phone (07) 3398 4992 | Scale | 1:2,000 (A4) | Job No. | J10721 | Model (Unmitigated) |



2 / 525 mm dia. outflow pipes @ 240.5 m AHD Scour protection at inlet and outlet Earth embankment to form detention basin 2 m wide weir @ 241.1 m AHD

> 241.5 242.02

N

Proposed Detention Basin

| TOPM | Drawn | JH | 6 Smalls | Road Mo | unt Morgan | Figure 7 |
|---|---------|------------|----------|----------|------------|-------------|
| STORM WATER CONSULTING | Checked | SNH | o smans | Roda, Ho | - | |
| 1/820 Old Cleveland Rd Carina QLD 4152 Phone (07) 3398 4992 | Date | 19/06/24 | 1 | | Conceptual | Stormwater |
| | Scale | 1:250 (A4) | Job No. | J10721 | | Layout Plan |

APPENDIX B

Photographs



Photograph 1 – Existing sheds on the site



Photograph 2 – Existing site condition at the location of proposed Shed 4



APPENDIX C

Rational Method Calculations

RATIONAL METHOD CALCULATIONS

Table C 1

а

1

Project: 6 Smalls Rd, Mount Morgan

Location: Point 1 - Total Flow - DS

Comments:

Developed Catchment

| Time of Concentration | | |
|--------------------------------------|------|--------|
| Upper Catchment Slope | 5.5% | |
| 100m sheet flow across average grass | 16.0 | min |
| Travel Length | 175 | metres |
| Fall | 15 | metres |
| Travel Time (Argue) | 1.5 | min |
| Delta for | 3.0 | |
| Time of Concentration | 20.5 | min |

Rainfall Data:

J10721

Rainfall Intensity Frequency Duration data for Mt Morgan (Rockhampton)

Sub-Areas and Runoff Coefficients

| Sub-Alea | s anu r | | JUEIIICI | ents | | | | | | | | | |
|-----------|---------|-------|----------|-----------|------------------------------|------|------------|------------------------------------|-------|---------|---------|-------|-------|
| | Area | C | 10 | Areas inc | eas included in Calculations | | | Separate c100 > 1.0 and c100 < 1.0 | | | | | |
| | ha | Exist | Dev | Condition | Area | C10 | C10 x A | C10 | C10 | C10 x A | C10 x A | Area | Area |
| Catchment | 3.93 | 0.00 | 0.78 | Developed | 3.93 | 0.78 | 3.07 | 0.78 | | 3.07 | | 3.93 | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | 3.93 | | Sum | | | 3.07 | 0.00 | 3.93 | 0.00 |
| | | | | | | _ | Total | | 0.780 | | 3.065 | | 3.930 |
| | | | | | | | Individual | 0.780 | 0.000 | 3.065 | 0.000 | 3.930 | 0.00 |

| | rge Cal | culation | | | | | | |
|--------|---------|----------|-----------|-------------|----------|----------|-----------|-------|
| | tc | | | 20.5 | | | | _ |
| C100>1 | | Average | c10 | 0.000 | | Total Ca | tchment | |
| | | | Area (ha) | 0.00 | | 3.9 | 3 ha | |
| C100<1 | c10 - 2 | Average | | 0.780 | | | | - |
| | | | Area (ha) | 3.93 | | | | |
| Depth | AEP | Fy | | oefficients | Rainfall | | Discharge | |
| Deptil | | • • • | Runon C | Jenneients | Kaintaii | m³/s | | |
| mm | % | | C100>1 | C100<1 | (mm/hr) | 1 | 2 | Total |
| 23 | 63 | 0.80 | 0.00 | 0.62 | 67.21 | 0.00 | 0.46 | 0.458 |
| 25 | 50 | 0.85 | 0.00 | 0.66 | 74.42 | 0.00 | 0.54 | 0.539 |
| 33 | 20 | 0.95 | 0.00 | 0.74 | 96.94 | 0.00 | 0.78 | 0.784 |
| 38 | 10 | 1.00 | 0.00 | 0.78 | 112.48 | 0.00 | 0.96 | 0.958 |
| 44 | 5 | 1.05 | 0.00 | 0.82 | 127.37 | 0.00 | 1.14 | 1.139 |
| 51 | 2 | 1.15 | 0.00 | 0.90 | 148.02 | 0.00 | 1.45 | 1.449 |
| 56 | 1 | 1.20 | 0.00 | 0.94 | 163.03 | 0.00 | 1.67 | 1.666 |
| 62 | 0.5 | 1.20 | 0.00 | 0.94 | 181.67 | 0.00 | 1.86 | 1.856 |
| 74 | 0.2 | 1.20 | 0.00 | 0.94 | 215.33 | 0.00 | 2.20 | 2.200 |

| - | | |
|-----|-----------|---------|
| EY | Discharge | % of |
| | m³/s | 63% AEP |
| 12 | 0.114 | 25% |
| 6 | 0.183 | 40% |
| 4 | 0.229 | 50% |
| 3 | 0.275 | 60% |
| 2 | 0.343 | 75% |
| 1.3 | 0.412 | 90% |
| 1 | 0.458 | 100% |

APPENDIX D

URBS Data

URBS Data Files – Existing Model

"Index", "Area", "UR", "UL", "I"
#1,0.00298,1.00,0.00,0.89
#2,0.00515,1.00,0.00,0.19
#3,0.00410,1.00,0.00,0.60
#4,0.00482,1.00,0.00,0.27
#5,0.00184,1.00,0.00,0.65
#6,0.00793,1.00,0.00,0.52
#7,0.00165,1.00,0.00,0.05
#8,0.00548,1.00,0.00,0.27
#9,0.00117,1.00,0.00,0.05
#10,0.00422,1.00,0.00,0.05

SmallsRd - Existing MODEL: Basic USES: L, U Default Parameters: alpha=1.20 m=0.8 Catchment File=10721 Ex.dat Rain #1 L=0.034 Route thru #2 L=0.051 #2 L=0.033 L=0.039 Add Rain Rould Store. 'n #3 Route thru #4 L=0.062 #4 L=0.029 Route thru Get. Add Rain #4 L=0.049 Route thru L=0.018 #7 #7 L=0.020 L=0.023 Add Rain Route thru #9 Add Rain #9 L=0.034 Store. Rain #5 L=0.042 Route thru #6 I Add Rain #6 L=0.065 Add Rain L=0.030 Route thru #8 L=0.024 L=0.040 L=0.067 #8 Add Rain Route thru #10 Store. Rain #10 L=0.056 Get. Get. Print. POINT-1 end of catchment details.

URBS Data Files – Developed Model (Unmitigated)

"Index", "Area", "UR", "UL", "I"
#1,0.00298,1.00,0.00,0.72
#2,0.00515,1.00,0.00,0.63
#3,0.00410,1.00,0.00,0.60
#4,0.00482,1.00,0.00,0.41
#5,0.00184,1.00,0.00,0.65
#6,0.00793,1.00,0.00,0.72
#7,0.00165,1.00,0.00,0.19
#8,0.00548,1.00,0.00,0.35
#9,0.00117,1.00,0.00,0.05
#10,0.00422,1.00,0.00,0.05

SmallsRd - Development MODEL: Basic USES: L, U Default Parameters: alpha=1.20 m=0.8 Catchment File=10721 Dev.dat Rain #1 L=0.034 Route thru #2 L=0.051 L=0.033 L=0.039 Add Rain #2 Roule Store. '~ #3 Route thru #4 L=0.062 #4 L=0.029 Route thru Get. Add Rain #4 L=0.049 Route thru #7 Add Rain #7 Route thru #9 L=0.018 L=0.020 L=0.023 Route thru #9 Add Rain #9 L=0.034 Store. Rain #5 L=0.042 Route thru #6 D Add Rain #6 L=0.065 Add Rain #6 L=0.030 Route thru #8 L=0.024 L=0.040 L=0.067 #8 Add Rain #10 Route thru Store. Rain #10 L=0.056 Get. Get. Print. POINT-1 end of catchment details.

URBS Data Files – Developed Model (Mitigated)

"Index", "Area", "UR", "UL", "I"
#1,0.00298,1.00,0.00,0.72
#2,0.00515,1.00,0.00,0.63
#3,0.00410,1.00,0.00,0.60
#4,0.00482,1.00,0.00,0.41
#5,0.00184,1.00,0.00,0.65
#6,0.00793,1.00,0.00,0.72
#7,0.00165,1.00,0.00,0.19
#8,0.00548,1.00,0.00,0.35
#9,0.00117,1.00,0.00,0.05
#10,0.00422,1.00,0.00,0.05

SmallsRd - Development1 MODEL: Basic USES: L, U Default Parameters: alpha=1.20 m=0.8 Catchment File=10721 Dev1.dat Rain #1 L=0.034 Route thru #2 L=0.051 L=0.033 Add Rain #2 Route thru #4 L=0.039 Store. L=0.062 #4 #3 Rain L=0.029 Route thru Get. Add Rain #4 L=0.049 L=0.018 Route thru #7 L=0.020 #7 Add Rain Route thru #9 T=0.023 Add Rain #9 L=0.034 Store. Rain #5 L=0.042 Route thru #6 I Add Rain #6 L=0.065 Add Rain #6 L=0.030 Route thru #8 L=0.024 Add Rain #8 L=0.040 L=0.067 Route thru #10 Store. Rain #10 L=0.056 Get. Get. Print. B1-IN DAM ROUTE VBF=0 NUMBER=26 0.000000 0.000000 0.012900 0.064762 0.025800 0.129524 0.038700 0.212857 0.051600 0.349524 0.064500 0.461905 0.094750 0.594286 0.125000 0.821193 0.155250 1.095741 0.185500 1.408671 0.215750 1.761924 0.264000 2.169466 0.312250 2.601511 0.360500 3.064595 0.408750 3.523067 0.457000 4.003636 0.525250 4.514286 0.593500 5.063236 0.661750 5.635081 0.730000 6.228844 0.798250 6.843665 0.892250 7.478775 0.986250 8.114440 1.080250 8.769083 1.174250 9.442137 1.268250 10.13308 { } { } Print. B1-OUT Print. POINT-1 end of catchment details.

Detention Basin Results

| AEP | URBS Basin | | | Discharge | | Inundation | | |
|------|------------|---------|--------|-----------|------|------------|----------------|----------------|
| | Inflow | Outflow | Level | Depth | Pipe | Weir | Area | Volume |
| | m³/s | m³/s | m AHD | m | m³/s | m³/s | m ² | m ³ |
| 6320 | 0.49 | 0.48 | 241.01 | 0.51 | 0.48 | 0.00 | 219.4 | 68.3 |
| 5000 | 0.56 | 0.54 | 241.06 | 0.56 | 0.54 | 0.00 | 235.1 | 81.9 |
| 2000 | 0.80 | 0.77 | 241.18 | 0.68 | 0.69 | 0.08 | 277.2 | 118.2 |
| 1000 | 1.04 | 1.02 | 241.27 | 0.77 | 0.78 | 0.23 | 310.2 | 146.8 |
| 0500 | 1.21 | 1.19 | 241.33 | 0.83 | 0.83 | 0.36 | 330.3 | 164.1 |
| 0200 | 1.44 | 1.41 | 241.40 | 0.90 | 0.88 | 0.53 | 355.3 | 185.8 |
| 0100 | 1.63 | 1.60 | 241.45 | 0.95 | 0.92 | 0.68 | 373.8 | 201.7 |



22 July 2024

Peacefield Egg Farms Pty Ltd 360 Allambie Lane Gumlow QLD 4815

ROCKHAMPTON REGIONAL COUNCIL APPROVED PLANS

These plans are approved subject to the current conditions of approval associated with **Development Permit No.: D/96-2024**

Dated: 16 December 2024

Attention: Barry Shonhan

Dated: 16 December 2024

Dear Barry,

RE: PROPOSED LAYER FARM EXTENSION – SIGHT DISTANCE ASSESSMENT

PSA Consulting has been engaged by Peacefield Egg Farms to provide traffic engineering advice regarding the access driveway for the proposed upgrades to the existing layer farm at 6 Smalls Road, Hamilton Creek. This technical note outlines the sight distance requirements concerning the northern access to the development. The assessment of sight distance has been undertaken on a desktop basis only, relying on aerial imagery and Google Streetview. No site visit has been undertaken to verify the findings.

According to the Capricorn Municipal Development Guidelines, the location of the intersection shall be evaluated for conformance with the criteria for Approach Sight Distance (ASD), Minimum Gap Sight Distance (MGSD), and Safe Intersection Distance (SISD). Table outlines the required ASD, MGSD, and SISD for the intersection with a speed limit of 50km/hr and a corresponding design speed of 60km/hr.

Table 1: Developments along Raff Lane Trip Generation (Source: PSA)

| Design Speed | ASD | MGSD | SISD |
|--------------|------|------|-------|
| 60 km/hr | 73 m | 83 m | 123 m |

To achieve the required approach sight distance (ASD), it is necessary to prune the tree located north of the access, as its canopy encroaches upon the sight envelope, as shown in Figure 1.

Connecting communities. Creating better places.

LAND USE PLANNING > DEVELOPMENT APPROVALS > TRANSPORT PLANNING > TRAFFIC ENGINEERING
 TRANSPORT PROGRAM MANAGEMENT AND OPERATIONAL READINESS > INFRASTRUCTURE





Figure 1: Approach Sight Distance (Source: Nearmap, PSA)

As illustrated in Figure 2, there are no conflicts within the sight envelope required to achieve minimum gap sight distance (MGSD). Therefore, no further mitigation measures are required.





Figure 2: Minimum Gap Sight Distance (Source: Nearmap, PSA)

The required sight envelope to achieve safe intersection sight distance (SISD) is shown in Figure 3.






Figure 3: Safe Intersection Sight Distance (Source: Nearmap, PSA)

Figure 4 demonstrates that the first tree south of the access has high branches and a narrow trunk, which will not obstruct the sight lines of the road. However, it is recommended to remove branches lower than 1.1m in height to ensure there is no obstruction present within the driver's sight line. Furthermore, the second and third tree must be removed to fully achieve required safe intersection sight distance (SISD).



Figure 4: Sight Distance Looking to the South (Source: Google Streetview)



In summary, it has been observed that while trees are within the sight envelope of required sight distances, there are no permanent obstructions that would prevent achieving the necessary sight distance. It is recommended to perform tree pruning and removal of the aforementioned vegetation to ensure safety at the site access.

I trust the above meets your requirements. If you have any questions, please don't hesitate to contact the undersigned.

Yours sincerely,

Bordy

Tim Boxall RPEQ 26741 Senior Traffic and Transport Engineer PSA Consulting (Australia) Pty Ltd

| VERSION | DATE | DETAILS | AUTHOR | AUTHORISATION |
|---------|--------------|---------|--------------------|--------------------------|
| 1 | 22 July 2024 | FINAL | Daina Ruth Aliboso | Tim Boxall RPEQ 26741 |